

# **BRUHATH BANGALORE MAHANAGARA PALIKE**

## **DASARAHALLI ZONE**

Office of the Executive Engineer Dasarahalli Division

### **MODIFIED SCHEDULE B**

Nam eof Work: Desilting and resetting of drain and re asphaltting to 5th B cross and 17th Cross and other cross roads at MEI Layout in ward no.14 Bagalagunte

Job Code: 014-18-000071

| SI | Description of Work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Unit | Qty     | Sanctioned Rates |                                        |
|----|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|---------|------------------|----------------------------------------|
|    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |      |         | In figures (Rs)  | In Words (Rs)                          |
| 1  | Removing and refixing stone slabs of drains and pointing in CM (1:3)                                                                                                                                                                                                                                                                                                                                                                                                                                              | Sqm  | 1101.60 | 100.00           | Rupees One Hundred Only                |
| 2  | KSRRB 300-2. Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3                                                                                                                                                                                          | Cum  | 518.40  | 270.00           | Rupees two hundred seventy Only        |
| 3  | KSRRB 15.2.1 Providing flush pointing to stone slab pavements, with cement mortar 1:3, after raking joints, nicely lining, including cost of materials, labour, curing complete as per specifications.                                                                                                                                                                                                                                                                                                            | Sqm  | 1035.00 | 33.00            | Rupees Thirty three Only               |
| 4  | Providing precast slab of 100 mm thick including cost of all materials, labour, curing, transportation, loading, unloading, etc., complete as per the direction of engineer in charge                                                                                                                                                                                                                                                                                                                             | Sqm  | 227.40  | 2200.00          | Rupees Two thousand Two hundred Only   |
| 5  | KSRRB 300-Compaction KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occurring during rolling including cost of all labour, HOM of machinery complete as per specifications. MORTH / Chapter 3                                                                                                                                                                                                                                | Sqm  | 1296.00 | 5.00             | Rupess Five only                       |
| 6  | KSRRB M400- Wet Mix Macadam KSRRB M400-17. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification | Cum  | 155.25  | 1800.00          | Rupess One thousand eight hundred only |
| 7  | KSRRB M500-6. Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. MORTH Specification No. 502 (P.No.158 I.No.21.6) Issue Basic Rate Date:02.11.2021 to till now                                                                                                                                             | Sqm  | 1296.00 | 30.00            | Rupees Thirty Only                     |

|    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |     |         |          |                                        |
|----|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|---------|----------|----------------------------------------|
| 8  | KSRRB 500-2. Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH specification clause 501 (P.No.158 I.No.21.2)                                                                                                                                                                                                                                                                        | Sqm | 4326.00 | 5.00     | Rupees Five only                       |
| 9  | KSRRB 500-7. Providing and applying tack coat using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH/Chapter 5                                                                                                                                                                                                                                                              | Sqm | 4326.00 | 10.00    | Rupees Ten only                        |
| 10 | KSRRB M500-17. Providing and laying dense graded bituminous macadam using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH table 500-10 complete in all respects complete as per specifications.. MORTH Specification No. 507 - using 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 4.5 % VG-30 Bitumen (P.No.161 I.No.21.15.2) | Cum | 64.80   | 8100.00  | Rupees Eight thousand One hundred only |
| 11 | KSRRB M500-19. Providing and laying bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 509 complete in all respects complete as per specifications. - using 40/60 TPH capacity H.M.P. with Mechanical Paver Gr-II (30 mm to 45 mm) with 6 % CRMB 55 (P.No.158 I.No.21.23.6) Issue Basic      | Cum | 173.04  | 10000.00 | Rupees Ten thousand only               |
| 12 | KSRRB M800-13.Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803 (P.No.185 I.No.24.15)                                                                                               | Sqm | 144.00  | 400.00   | Rupees Four hundred only               |

  
Signature of the Contractor

  
Executive Engineer  
Dasarahalli Division